OFFICE OF THE SUPERINTENDENT, GOVERNMENT GARDENS IN MYSORE, LAL-BAGH, BANGALORE.

Dated 23rd July 1935.

Notice is hereby given that separate sealed tenders will be received at the Office of the Superintendent, Government Gardens in Mysore, Lal-Bagh, Bangalore, up to 4 P.M., on 15th August 1935 for (A) annual repairs and special works to be done to buildings, culverts, etc., (B) special repairs to roads, (C) earthwork in Lal-Bagh and other Gardens and Parks, up to the end of June 1936.

2. Tenders should be submitted on printed forms (which may be obtained from the office of the undersigned) showing the rates at which different itmes specified will be executed.

3. Each tender must be accompanied by the Treasury Duplicate Chellan for having remitted rupees one hundred in cash as earnest money, and it should be superscribed "Tender for Annual Repairs and Special Works of Buildings, etc.," "Special Repairs to Roads," "Earth Work," in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Superintendent, Government Gardens in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be cancelled and his earnest money will be forfeited to Government.

6. The successful competitor whose tender is accepted will be informed in due course. No enquiries regarding the acceptance or rejection of tender will receive any reply.

7. The earnest money on rejected tenders will be returned.

8. Rate should be quoted for each item of work.

9. Percentage rates either below the estimated amount or the lowest tender will not be accepted.

10. In case of the non-tendered item, the departmental rates should be accepted by the contractor.

11. The undersigned reserves the right to get any work executed by departmental agency.

12. No claims for enhanced rates should be preferred at any time during the period of contract.

13. In all matters of dispute regarding quantity of work or rates, etc., the decision of the Superintendent, Government Gardens in Mysore, is final.

14. After completion of each estimated work, final measurements will be taken and checked, and the bill concerned will be arranged for payment.

Sl. No.	Items	Per	Rate to be given
			Rs. a. p.
	A. BUILDINGS—Annual Repairs and Special Works.		
1	Earthwork excavation for foundation and filling in basement with consolidation :—		
	(*a*) Ordinary soil	C.yd.	
	(*b*) Hard soil	,,	
2	Building foundation, burnt stone in mud	C.ft.	
3	Do stone in mortar	,,	
4	Basement, burnt stone in mud	,,	
5	Do in mortar	,,	
6	Walls, stone in mud	,,	
7	Do mortar	,,	
8	Do burnt brick in mud	,,	
9	Do do in mortar	,,	
10	Arch work, burnt brick in mud including centering	,,	
11	Do mortar including centering	,,	
12	Burnt stone dry wall and rivetment	,,	
13	Mud wall	,,	
14	Burnt stone slabs 5″ to 6″ thick roughly dressed including cement pointing	Sq. ft.	
15	Do with one line dressing including cement pointing	,,	
16	Do with two lines dressing including cement pointing	,,	
17	Removing and refixing old stone slabs with one line dressing for steps, etc.	,,	
18	Cutting grooves in slabs for pillars	Each	

Sl. No.	Items	Per	Rate to be given Rs. a. p.
19	Stone slab pillars with grooves cut	Sq. ft.	
20	Plastering with mortar stone wall	Square	
21	(*a*) Do brick wall	,,	
	(*b*) Do (rough plastering)	,,	
22	Plastering with cement stone wall	,,	
23	Do brick wall	,,	
24	Plastering with clay	,,	
25	Pointing with mortar	,,	
26	Pointing with cement	,,	
27	White-washing, two coats, including petty repairs	,,	
27a	Colour washing, two coats including petty repairs, including a coat of white-washing	,,	
28	Building coping for a wall of 9″, 1⅛′ and 1½′ thick including chunam plastering	R.ft.	
29	Repairs to coping and patty	,,	
30	Repairs to caps of plasters in compound wall	Each	
31	Painting two coats of deep green or chacolate or silver gray or signar red paint including cleaning the old paint to doors, windows, etc.	Square	
32	Painting white paint to doors, windows, etc., two coats after cleaning the old paint	,,	
33	Painting two coats of aluminium paint after cleaning the old paint	,,	
34	Wood oiling, two coats	,,	
35	Removing broken chunam plastering and cement plastering the ornamental parapet walls of culverts and steps	R.ft.	
36	Repairing the ornamental parapet wall of Balastrades with chunam	,,	
37	Cement washing, two coats including petty repairs	Square	
38	Distemper washing, two coats including petty repairs	,,	
39	Calcarium washing, two coats including petty repairs	,,	
40	Renewing glass panes ⅛″ thick	Sq.ft.	
41	Roofing with first class Mangalore tiles with teak reapers	Square	
41a	Pucca terrace roofing complete	,,	
42	Jack arch roofing complete	,,	
43	Roofing with re-inforced concrete complete	,,	
44	Roofing with 1½″ thick cuddapah slabs complete	,,	
45	(*a*) Removing old Mangalore tiled roof and refixing	,,	
	(*b*) Teakwood wrought and put up	C.ft.	
	(*c*) Jungle wood wrought and put up	,,	
46	(*a*) Renewing ⅛″ thick glasses for roof with clearing the grooves allowing air space	Sq.ft.	
	(*b*) Providing wire netting with iron stays and teak reapers complete above glass roof	,,	
47	Providing expanded metal pannels with teakwood frame to the open spaces between stone posts and fixing with iron clamps	,,	
47a	Providing expanded metal partition with teakwood frames with a double door way in the centre with fittings	,,	
48	Flooring with ganite slabs 4″ thick one line dressed over surki concrete 3″ thick including cement pointing	,,	
49	Do over sand bed including cement pointing	,,	
50	Flooring with Cuddapah slabs 1″ thick over surki concrete 3″ thick including cement pointing	,,	
51	Teakwood doors with panel shutters	,,	
52	Do with battened shutters	,,	
53	Teakwood windows with iron bars and glazed and panel shutters	,,	
54	Do with glazed shutters only	,,	
55	Do with panel shutters only	,,	
56	Providing expanded metal to existing windows of glazed shutters in the frame towards the shutters by deepening the groove	,,	
57	Building old stone in mud for foundations, walls, cisterns, etc.	C.ft.	
58	Do in mortar do	,,	
59	Do old brick in mud do	,,	
60	Do old brick in mortar do	,,	

Sl. No.	Items	Per	Rate to be given
			Rs. a. p.
61	Tarring to wood or wall	Square	
62	Stone pitching (with new stones)	,,	
63	Do (with old stones provided)	,,	
64	Curb stones 4″ thick, 12″ width with top dressed one line and rounded including fixing	R.ft.	
65	Combined white and colour washing two coats to ornamental parapet walls	,,	
66	Renewing roofing Mangalore tiles	Each	
67	Do roofing ridge tiles	,,	
68	New cornice work 6″ thick	R.ft.	
69	Do 9″ do	,,	
70	Repairing cornice with mortar 6″ thick	,,	
71	Do 9″ thick	,,	
72	Stone jelly in chunam concrete	C.ft.	
73	Surki concrete	,,	
73a	Stone jelly in cement concrete	,,	
74	Building new ornamental parapet wall with pillar foundations of 2 ft. cube, covered with 6″ thick stone slabs of 2 ft. width and the parapet with burnt brick in mortar and the balustrades of cement mould and cement plastering as per design in the Lal-Bagh, complete	R.ft.	
75	Do ornamental parapet as per design in the Terrace Garden near big fountain in Lal-Bagh	,,	
	B. ROADS—Special Works.		
76	Picking and forming laterite or metal road surface	Sq.yd.	
77	Spreading and consolidation with heavy stone roller of laterite or metal with gravel and sand	C.yd.	
78	Watering charges	Square	
79	Barricading and night watch with red lamps	Daily	
	C. EARTHWORK.		
80	Digging pits, trenches, etc., with a lead of 20 yards	C.yd.	
81	Filling earth for raising surfaces of maidan or roads with a lead of half mile in Park area	,,	
82	Silt clearing in ponds, channels, etc., and filling the hollows, etc., within a distance of one furlong	,,	
83	Silt cleaning in the chambers of the Septic Tank in the Horticultural Farm including baling out water	,,	
84	Turfing	Square	
85	Turf plastering with hariyali (as per specification)	,,	

M. K. SITHARAMA CHETTY,
Superintendent.

MYSORE RAILWAYS.

OFFICE OF THE TRAFFIC MANAGER, MYSORE.

Notice dated 25th July 1935.

With effect from 1st August 1935, Nos. 86 and 91 trains between Hassan and Arsikere will be cancelled and Nos. 87 and 90 Shuttle trains extended up to Hole-Narsipur and run daily to the following time-table.—

	No. 87.				No. 90		
		H.	M.			H.	M.
Arsikere	D.	8	45	Hole-Narsipur	D.	16	30
Hassan	A.	10	28	Hassan	A.	17	40
	D.	11	00		D.	17	45
Hole-Narsipur	A.	12	06	Arsikere	A.	19	30

For detailed timings, see sheet time-tables which will be exhibited at stations shortly.

H. D. SINCLAIR,
Traffic Manager.